



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

2213 / M-10

QUOTATION NOTICE

दिनांक:.....

01/03/2024

To,

M/s.....

.....

The sealed quotations are invited for P/L water supply drainage pipe line for canteen at R.H hostel the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated

...11/03/2024...

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Taking out existing CC interlocking paver blocks from footpath central verge, including removal of rubbish etc. disposal of unservicable material to the dumping ground for which payment shall be made separately and stcking of serviceble material within 50 meter lead as per direction of engineer incharge.	16.50	Sqm	
2.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5m lead upto 50m and dressing of sides and rammings of bottom	12.38	Cum	
3.	M-150 Class 230mm thick brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc. for proper completion of the work.	0.27	Cum	
4	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	1.44	Cum	
5	P/L 40mm thick cements concrete flooring with floating coat of neat cement in 1:2:4 cement, coarse sand 20mm stone grit.	2.25	Sqm	
6	laying old cement concrete interlocking paver block of any design shape laid in over 50mm thick compacted bed of coarse sand filling the jointes with fine sand etc. all complete.	16.50	Sqm	
7	P/F 25mm dia CPVC pipe having thermal stability for hot & cold water supply including al CPVC plain & brass threaded fittings this includes jointes of pipes & fittings with one step CPVC solvent cement trenching, refilling & testing joints complete.	45.08	Rmt	
8	P/F CPVC ball valve 25mm dia.	01	No.	
9	P/F PVC pipe 100mm dia of appd 6kg pressue	21.78	Rmt	
10	P/F PVC N trap 110mm dia.	01	No.	
11	P/F PTMT PVC bib cock make of appd quality	01	No.	
12	S/F wash basin white glazed 22"x16" complete with pillar cock, bracket, waste jali, waste pipe, PVC connection etc	01	No.	
13	Providing labour for cleaning of site and collecting malwa	03	Nos.	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.

Roy
JE

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग



फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org



पत्रांक: दिनांक:

4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.



Yours faithfully


(Suresh Kumar) 
(Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer

No. 2213/114 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 4/03/24 To 11/03/24
3. Sri T.C.Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar) 
(Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer


JE