



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 वेबसाइट : www.kgmu.org.

पत्रांक: -----

2007/M/10

दिनांक:.....
20/01/24

QUOTATION NOTICE

To,
M/s.....
.....
.....

The sealed quotations are invited for repair and painting work of low height boundary wall including grill and other misc work in front of S P hostel from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 24/01/22/24...

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	1.20	Sqm.	
2.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	1.20	Sqm.	
3.	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	1.20	Sqm.	
4.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	1.20	Sqm.	
5.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	94.40	Sqm.	
6.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	94.40	Sqm.	
7.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	363.09	Sqm.	
8.	P/L cement concrete in 1:2:4 cement ,course sand 20mm stone grit.	1.27	Cum.	
9.	P/L 15mm cement plaster 1:3(1 cement :3course sand) finished with a floating coat of neat cement on the rough side of single or half bruck wall.	20.15	Sqm.	
10.	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	107.01	Sqm.	

Jasvaidh
J.E



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 वेबसाइट : www.kgmu.org.

पत्रांक: -----

दिनांक:


11.	P/L matt finished vitrified tile of size 300x300x9.8 mm having with water absorption less than 0.5% and conforming to IS; 15622 of approved make in all colours and shades in for outdoor floors such as foothpath, court yard, multi modals location etc, laid 20 mm thick base of cement mortar 1:4(1 cement :4 course sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigment etc. complete as per direction of E/I.	2.00	Sqm.	
12.	S/F PVC Pipe of approved quality 6kg 100mm dia nominal bore.	6.10	Rmt.	
13.	S/F PVC Pipe of approved quality 6kg 150mm dia nominal bore.	4.00	Rmt.	
14.	Providing welding machine with welder for Repair of old M.S doors and windows	02	Nos.	
15.	Providing sweeper with helper for cleaning of drain.	02	Nos.	
16.	Providing labour (unskilled) for cleaning of site and collecting malwa.	05	Nos.	
17.	Cartage for disposal of malwa upto 10km away from the site.	2.71	Cum.	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


No. 2007/MAC of DT. 5.E 20/1/24

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow. 20/1/2024
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU Website from date 21/1/24..... To 29/1/24
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Karuna Nidhi, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


5.E 20/1/24