



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

1483/M10

### QUOTATION NOTICE

दिनांक

31/10/2023

To,

M/s.....


.....

The sealed quotations are invited for : Repairing of Staircase with MS angles . Removal of unwanted plant & cleaning of roof and miscellaneous work at main building, KGMU. The details of quotation notice can be seen at website www.kgmcindia.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 06/11/2023

Details of work as given below:-

S.NO	Particulars	Quantity	Unit	Rate
1	Dismantling cement concrete or brick or granolithic floor, including base concrete and including stacking of dismantled material as directed by the engineer in charge with in a distance of 60mtr.	32.28	Sqm	
2	Dismantling sundried brickwork including stacking of dismantle material as directed by engineer in charge with in a distance of 60mtr (200 ft)	1.66	Cum	
3	Dismantling existing plaster including disposal of refuse as directed by the engineer- in- charge with in a distance of 60mtr (200 ft).	18.45	Sqm	
4	Half brick masonry with common burnt clay brick class 150 in superstructure above plint level upto floor 5 <sup>th</sup> level. Cement mortar 1:3 (1 cement: 3 coarse sand)	1.80	Sqm	
5	Brick work with common burnt clay brick of class-150 in superstructure above plinth level up to floor 5 level in all shape and sizes in: Cement mortar 1:4 ( 1 cement: 4 coarse sand).	1.66	Cum	
6	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand ).	18.45	sqm	
7	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	18.45	Sqm	
8	Providing and laying of 62mm thick cement concrete flooring with concrete hardner topping on a reinforcement of murga jail , under layer 50mm thick cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 stone aggregate 20mm nominal size ) and top layer 12mm thick cement hardening of mix 1:2( 1 cement hardener mix : 2 graded stone aggregate 6mm nominal size ) by volume , hardening compound mixed @2 ltr per 50kg of cement or as per manufactures specification . this includes cost of cement slurry , but excluding the cost of nosing of steps etc complete.	32.28	Sqm	
9	Providing of chemical for removal of unwanted plants.	25	Ltr	
10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	35	KG	

Handwritten signature/initials



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmciindia.edu.




पत्रांक: -----

			दिनांक: .....
11	Providing of 1 Sweeper for 4 days, per pair with tools.	4	Nos
12	Providing plumber with helper repairing for sanitation work.	4	Nos
13	Semi skilled labour for unwanted plant cutting and for miscellaneous civil work.	33	Nos
14	Providing cartage for disposal of malwa, refuse material from site as per direction of engineer in charge.	27.10	Cum

### Terms & Conditions

- 1.G.S.T and labour cess shall be paid or deducted as per rules applicable.
- 2.The work will be completed within given time.
- 3.Quantity can be increase or decrease as per requirements.
- 4.Conditional quotations are liable to be rejected.
- 5.The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


Yours faithfully

  
(Dinesh Kumar Raj)  
Superintending Engineer  
 

No. 1483/1410 / of DT.

Copy for information and necessary action to:-

- 1.Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 30/10/2023 To 01/11/2023
3. Sri Shailendra Singh, Executive Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Anjani kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
6. Notice Board.

  
(Dinesh Kumar Raj)  
Superintending Engineer  
