



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

1833 / 116

QUOTATION NOTICE

दिनांक:.....

29/12/2023

To,

M/s.....

.....

The sealed quotations are invited for P/L sewer line in toilet block of female ward at first floor of IARI cardiology KGMU. The details of quotation notice can be seen at website www.kgmucollege.org and on the Notice board of the office of undersigned. Registered contractors of KGMU may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 29.12.2023.

Details of work as given below:-

| S.No. | Particulars | Quantity | Unit | Rate |
|-------|--|----------|------|------|
| 1. | Dismantling old tile flooring including disposal of refuse as directed by Engineer-in-charge. | 12.76 | Sqm. | |
| 2. | Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge. | 17.28 | Sqm. | |
| 3. | P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit. | 0.51 | Cum. | |
| 4. | P/L of 62mm thick cement concrete flooring with concrete hardner topping, under layer 50mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) and top layer 12mm thick cement hardner of mix 1:2 (1 cement hardner mix : 2 graded stone aggregate 6mm nominal size) by volume, hardner compound mixed @2 liter per 50kg of cement or as per manufacturer's specification, this includes the cost of cement slurry, but excluding the cost of nosing of steps etc. complete. | 12.76 | Sqm. | |
| 5. | Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete. | 17.28 | Sqm. | |
| 6. | P/L ceramic floor tiles in size 300x300mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete. | 12.76 | Sqm. | |
| 7. | Distemping with oil bound distemper two coat of approved brand on old surface to give an even shade including all material, labour T&P etc. complete. | 30.04 | Sqm. | |
| 8. | Painting two coats with Superior synthetic enamel paint in old surface including supply of labour material t&p etc. complete. | 4.92 | Sqm. | |
| 9. | S/F of white glazed Orissa Pan 580 mm dia complete. | 02 | Nos. | |
| 10. | S/F of wash hand basin heavy quality make of approved brand with pillar cock, bracket, pvc connection, waste pipe complete. | 01 | No. | |
| 11. | P/F 600x450mm beveled edge mirror of superior glass complete with 6mm thick hard board fixed to wooden cleats with C.P. brass screws and washers complete. | 01 | No. | |
| 12. | S/F 10 Lit PVC low down cistern for appd. Quality in completed. | 02 | Nos. | |
| 13. | S/F of C.P soap dish of approved quality make cera or equivalent. | 02 | Nos. | |

T. Roy.
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

दिनांक:

| | | | | |
|-----|--|-------|------|--|
| 14. | S/F of C.P floor jaali heavy quality 100mm dia. | 02 | Nos. | |
| 15. | S/F PVC waste pipe 32mm dia 600m long. | 01 | No. | |
| 16. | S/F PVC bib cock 15mm dia prayag make or equivalent. | 03 | Nos. | |
| 17. | S/F PVC pillar cock 15mm dia prayag make or equivalent. | 01 | No. | |
| 18. | S/F PVC angle valve 15mm dia prayag make or equivalent. | 03 | Nos. | |
| 19. | S/F PVC connection 600mm long Prayag make or equivalent. | 03 | Nos. | |
| 20. | P/F CPVC pipes 20mm dia., having thermal stability or hot & cold water supply, including all CPVC plain and brass threaded fittings, l/c fixing the pipe with clamps at 1m spacing. This includes jointing of pipes and fitting with one step CPVC solvent cement and the cost of trenching and refilling including testing of joints complete as per direction of E/I complete. | 11.95 | Rmt. | |
| 21. | P/F of Hepco red HCI pipe with socket including fitting 100mm dia. | 17.60 | Rmt. | |
| 22. | P/F C.I Collar socket 100mm dia. Of approved quality complete. | 03 | Nos. | |
| 23. | P/F C.I door tee 100mm dia. Of approved quality complete. | 01 | No. | |
| 24. | P/F C.I P-trap 100mm dia. Of approved quality complete. | 04 | Nos. | |
| 25. | Providing Plumber with helper for removing of old fittings. | 01 | No. | |
| 26. | Providing labour for cleaning of site and collecting malwa. | 06 | Nos. | |
| 27. | Cartage for disposal of malwa up to 10km away from site. | 8.10 | Cum. | |

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


T. Roy
JE

No. 1833/MC / of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.





किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

- दिनांक:.....
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 29/12/2023 To 15/01/2024
 3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
 4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
 5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


JE