



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

2039/MSO

दिनांक: .....

29/01/2024

**QUOTATION NOTICE**

To,

M/s.....

.....

.....

The sealed quotations are invited for repairing of old damaged floor tiles, fixing of water supply pipe line on roof and other misc. work at shatabdi Phase-1 the detail of quotation notice can be seen at website [www.kgmu.org](http://www.kgmu.org) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 25/02/2024  
Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I	28.19	Sqm	
2.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	1.05	Sqm	
3.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	1.14	Cum	
4.	M-150 Class 230mm thick brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc. for proper completion of the work.	0.12	Cum	
5.	P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete	0.15	Sqm	
6.	P/L floor tiles in size 600x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds laid on 20mm thick cement mortar in 1:4 including grouting of joints with white cement and matching pigment etc. complete.	7.20	Sqm	
7.	P/L wall tiles 300x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment.	0.90	Sqm	
8.	P/L pavit floor tiles in size 300x300x9mm with water absorption less then 0.05% and conforming to IS: 15622 of approved make in all colours and sheds layd on 20mm thick base of 1:4 cement coarse sand in all complete.	20.99	Sqm	
9.	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete.	1.48	Rmt	
10.	15mm cement plaster 1:3 cement coarse sand finishing with a floating coat of neat cement.	0.91	Sqm	
11.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work	0.92	Sqm	
12.	Providing labour charge for repairing of old aluminum door.	4.60	Sqm	
13.	P/F rubber beading for fixing of glass in aluminum door and partition.	7.34	Rmt	
14.	P/F aluminum clip for fixing of glass in aluminum door and partition.	2.64	Rmt	
15.	P/F 32mm dia G.I pipe complete with G.I fittings and clamps I/C cuttings and making good the walls etc.	12.10	Rmt	
16.	P/F 25mm dia G.I pipe complete with G.I fittings and clamps I/C cuttings and making good the walls etc.	2.20	Rmt	

1/Roy



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: .....

दिनांक: .....


17.	P/F 20mm dia G.I pipe complete with G.I fittings and clamps I/C cuttings and making good the walls etc.	4.35	Rmt	
18.	Providing and fixing CPVC pipes 25mm dia including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing this includes jointings of pipes & fittings	30.60	Rmt	
19.	P/F G.I tee 32mmx20mm dia.	02	Nos.	
20.	P/F G.I socket 32mm dia.	02	Nos	
21.	P/F G.I socket 25mm dia.	01	No.	
22.	P/F G.I nipple 32mm dia 150mm long.	02	Nos	
23.	P/F G.I long screw 25mm dia	01	No.	
24.	P/F G.I long screw 20mm dia	03	Nos	
25.	P/F G.I Elbow 20mm dia	06	Nos	
26.	P/F brass ball valve 20mm dia make NMV	03	Nos	
27.	P/F PTMT 25mm dia ball cock of appd quality colour and make complete with epoxy coated aluminum rod with L.P plastic ball	02	Nos	
28.	Making connection of G.I distribution branch with G.I main of following size 25 to 40mm dia by P/F tee, including cutting and treading the pipe etc complete.	02	Nos	
29.	Providing Plumber with helper for repairing of old fitting and making water connections	02	Nos	
30.	Cartage for disposal of malwa up to 10km away from site	8.70	Cum	
31.	Providing labour charge for cleaning of roof and collecting malwa	8.00	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


  
(Suresh Kumar)


  
(Dinesh Kumar Raj)  
Executive Engineer Superintendent Engineer

No. 2030/ MME of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 21.11/2024 To 25/12/2024
3. Sri T.C.Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

  
(Suresh Kumar)  
Executive Engineer

  
(Dinesh Kumar Raj)  
Superintendent Engineer

