



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

2129/M10

QUOTATION NOTICE

दिनांक:.....
18/02/2024

To,

M/s.....
.....
.....

The sealed quotations are invited for Providing and fixing aluminium partition including repairing and painting work of office in basement of general surgery department KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Registered contractors of kgmu may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 25/02/2024

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of dismantled as directed by engineer incharge.	2.73	Sqm.	
2.	P/F anodised aluminium work for doors, windows and ventilators with extruded built up standard tabular sections/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc	18.93	Kg.	
3.	P/F anodised aluminium work for partitions with extruded built up standard tabular sections/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc	107.85	Kg.	
4.	P/F float glass panes of 5mm thick in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per directions of E/I.	6.48	Sqm.	
5.	P/F nova pan board in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/neoprene gasket etc. complete as per the architectural drawings and the directions of E/I.	3.60	Sqm.	
6.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	14.17	Sqm.	
7.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	2.73	Sqm.	
8.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	14.17	Sqm.	
9.	Distemping with oil bound distemper two coat of approved brand on old Surface to give an even shade including all material , labour T&P etc. complete.	130.91	Sqm.	
10.	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	12.40	Sqm.	
11.	P/F of S.S hinges 100mm long with stainless steel screws etc. complete.	04	Nos.	
12.	P/F aluminium handle 100			



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu


पत्रांक: -----


			दिनांक:.....
13.	P/f Aluminium sliding door bolt with 16mm dia and 200mm long.	01	No.
14.	P/f Aluminium tower bolt with 10mm dia and 250mm long.	01	No.
15.	Providing labour for cleaning of site and collecting malwa.	02	Nos.

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


P. Roy
JE

No. 2129/M10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 16/02/24 To 22/02/2024
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


P. Roy
JE