



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

2153/110

दिनांक: 21/02/2024

QUOTATION NOTICE

To,

M/s.....

.....

The sealed quotations are invited for P/F PPGI shed and false ceiling including repairing and painting of office room in research cell at old administrative block KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 27/02/2024

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	18.90	Sqm.	
2.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	18.90	Sqm.	
3.	Distempering with oil bound distemper two coat of approved brand on old Surface to give an even shade including all material , labour T&P etc. complete.	18.90	Sqm.	
4.	GI Metal Ceiling Clip in plain Beveled edge global white color tiles of size 600x600 and 0.5 mm thick with 25 mm height, made of G I sheets.	17.21	Sqm.	
5.	Providing and fixing precoated galvanised iron sheets 0.50mm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws with EPDM seal,excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	38.94	Sqm.	
6.	P/F GI metal tile in plain beveled edge global white colour tiles of size 600X600mm and 0.5mm thick complete.	11.52	Sqm.	
7.	P/f double action hydraulic floor spring of approved brand and manufacture with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. With stainless steel cover plate minimum 1.25 mm thickness complete.	03	Nos.	
8.	Repairing of old aluminium doors with 8mm dia. Fully threaded tie rod with nut and washer including placing on proper position in aluminium door frame.	6.30	Sqm.	
9.	Providing labour for dismantling old shed and false ceiling, cleaning of site and collecting malwa.	04	Nos.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.

IRoy
TE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग


फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu


पत्रांक: -----

दिनांक:.....

3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

No. 2153/M10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 21/02/2024 To 22/02/2024
3. Sri Suresh Kumar, Executive Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
6. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


P. Ray.
JE