



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक: 2042 / एम-10 / 2024

दिनांक: 31/01/2024

QUOTATION NOTICE

To,

M/s.....

.....

The sealed quotations are invited for Repairing, painting and other misc.work of 4 room and other misc. work at Buddha hostel at KGMU at kgmu from the registered contractor of KGMU. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 07/02/2024

Details of the work as given below-

S.No	Particular	Qty	Unit	Rates
1.	Scrapping old white or coloured wash etc including disposal of refuse material as directed by Engineer in charge	182.13	Sqm	
2.	P/L of Birla white putty for making good smooth surface.	182.13	Sqm	
3.	Distempering with oil bound distemper two coat of approved brand on old surface togive and even shade including all material, labour T&P etc. complete.	299.32	Sqm	
4.	Enamel painting in two coat	32.28	Sqm	
5.	Fly proof stainless steel grade 304 wire gauze with 0.5mm dia.wire and 1.4mm wide aperture with matching wood beadings.	3.60	Sqm	
6.	S/F 4mm thick float glass panes in windows with wooden beadings.	10.80	Sqm	
7.	P/F PVC pipe 100mm dia 6kg pressure ISI make	2.00	Rmt	
8.	P/F double scaffolding system (cup lock type) on the exterior side of building/structure,upto 25 metre height,above ground level,including additional rows of scaffolding in stepped manner as per requirement of site,made with 40mm dia. M.S Tube placed 1.5 metre center to center.horizontal and vertical tubes joint with cup and lock system with M.S Tubes,M.S Tubes challis,M.S clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable conditionfor execution of work of cleaning and/or pointing and/or applying chemical and removing it thereafter.The scaffolding system shall be stiffened with bracings,runners,connecting with the building etc,wherever required,if feasible for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge.	13.50	Sqm	
9.	P/f of 10 lit P.V.C. low down cistern for appd. quality in completed.	1	Nos	
10.	Providing and fixing of P.V.C. waste pipe 32mm dia. 600mm long.	4	Nos.	
11.	Providing and fixing C.P. Brass spandle for basin mixer/wall mixer.	5	Nos.	
12.	P/F P.V.C Long body Bib cock 15 mm (make of prayag).	4	Nos	
13.	P/F sink jail 100mm dia.	3	Nos.	
14.	P/F of siphon.	1	Nos.	
15.	P/F C.P. over head shower of size 150x150mm of approved quality cera,prayag or equivalent including labor T&P complete.	1.00	Nos.	
16.	Water Proofing treatment for joints of C.I/PVC pipe with resin based water proofing chemical including fiber glass matt and fine powder width of chemical coating on joint not less than 250mm on any dia. of pipe. Applying chemical	5	Nos.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu


पत्रांक:..... / एम-10 / 2024


दिनांक:.....

18.	Providing plumber with helper for sanitary fitting	4	Nos.	
19.	Providing Sweeper for cleaning of bathroom.	4	Per day	

Terms & Conditions

1. G.S.T and labourcess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


(Anupam Mishra)
Executive Engineer

Yours Faithfully

(Dinesh Kumar Raj)
Superintending Engineer


No. 2042/M-10

Date.....


Copy for Information and necessary action to:

1. Registrar, K.G.M.U. U.P. Lucknow
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 31/01/24 To 07/02/24
3. Sri Yashvant Singh, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Sumit Kanaujia, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board


(Anupam Mishra)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer