



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----

2238/M-10

QUOTATION NOTICE

दिनांक:

07/03/2024

To,

M/s.....

.....

.....

The sealed quotations are invited for Repairing work , painting work and miscellaneous work at Respiratory Medicine department, KGMU. The details of quotation notice can be seen at website www.kgmu.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 14/03/2024

Details of work as given below:-

S.NO	Particulars	Quantity	Unit	Rate
1	Dismantling stone flagged or tile floor, including stacking of dismantling material as per direction by the E/I.	2.52	Sqm	
2	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	108.65	Sqm	
3	Brick work with common burnt clay (non modular) bricks of class-150 in superstructure above plinth level up to floor 5 level in all stage and size in: Cement mortar 1:6 (1 cement : 4 coarse sand).	0.31	Cum	
4	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand).	1.33	Sqm	
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc complete. 40mm thick with 20mm nominal size stone aggregate.	6.14	Sqm	
6	Applying coat of water thinnable cement primer of approved brand and manufacture on new plastered wall surface.	1.33	Sqm	
7	Providing and applying white cement based putty of average thickness 0.60 mm of approved brand and manufacture, over the old plastered wall surface to prepare the surface even and smooth complete.	108.65	Sqm	
8	Enamel painting in two coat.	65.65	Sqm	
9	Oil bound distemper in two coat.	362.15	Sqm	
10	Providing and laying finish vitrified tile of size 300x300x9.8mm having with water absorption less than 0.5% and conforming ti IS: 15622 of approved make in all colour and shades in for outdoor floor such as footpath, courtyard, multi modals location etc laid on 20mm thick base of cement mortar 1:4 in all shapes and pattern including grouting the joint with white cement mixed with matching pigments etc. complete as per direction of engineer in charge.	2.52	Sqm	
11	Providing and laying in position cement concrete of specified grade : 1:6:12 (1 cement : 6 coarse sand, 12 graded brick aggregate 40mm.	1.21	Cum	
12	Laying old cement concrete interlock paver block of any design/shape laid in required line , level , curvature ,colour and pattern over and including 50mm thick compacted bed of course sand, filling the joint with fine sand etc. all complete as per the direction of engineer-in- charge (old CC paver block shall be supplied by the department free of cost).	7.11	Sqm	
13	Providing and laying of interlocking concrete block pavement	3.50	Sqm	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----

		दिनांक:.....	
14	having thickness 60mm. P/F 600x450mm beveled edge mirror of superior glass complete with 6mm thick hard board fixed to wooden cleats with C.P brass screw and washer complete.	1	Nos
15	Providing of concentrated Acid for removal of solid disposal in C.I drainage lines with cost of material, labour, T&P complete in all respect.	10	Ltr
16	P/F of CPVC pipes of approved quality including cost of material, labour, T&P complete in all respect. 50 mm dia	6.12	Rmt
17	P/F of stainless steel sink with drain board 610X510X200mm including cost of material, labour, T&P complete in all respect.	1	Nos
18	Semi skilled labour for unwanted plant cutting and for miscellaneous civil work.	12	Nos
19	Sweeper per pair with tools	8	Nos
20	Providing plumber with helper repairing for old sanitation work.	4	Nos
21	Providing cartage for disposal of malwa, refuse material from site as per direction of engineer in charge.	15.37	Cum

Terms & Conditions

- 1.G.S.T and labour cess shall be paid or deducted as per rules applicable.
- 2.The work will be completed within given time.
- 3.Quantity can be increase or decrease as per requirements.
- 4.Conditional quotations are liable to be rejected.
- 5.The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

No. 2238/MO of DT.

Copy for information and necessary action to:-

- 1.Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 21/03/2024 To 14/03/2024
3. Sri Anjani kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

