



कग जाज चौकेत्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: 2064/ME

QUOTATION NOTICE

दिनांक: 02/02/2024

To,


M/s.....

The sealed quotations are invited for Repairing and painting work of front boundary wall including other misc. work at central library KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Registered contractors of kgmu may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 09/02/2024

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	48.10	Sqm.	
2.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	3.45	Sqm.	
3.	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	32.54	Sqm.	
4.	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	2.60	Cum.	
5.	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	15.66	Sqm.	
6.	P/L of appd. Quality unipaver rubber molding interlocking tiles not less than 30MPa including leveling and dressing of surface to required level and slope, filling joints local sand and also including the cost of all material, labour T&p complete.	16.58	Sqm.	
7.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	1.30	Cum.	
8.	P/L matt finished vitrified tile of size 300X300 having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 complete as per direction by E/I.	6.74	Sqm.	
9.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	48.10	Sqm.	
10.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	175.29	Sqm.	
11.	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	36.98	Sqm.	

T. Roy,
J.E.



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu


पत्रांक: -----

			दिनांक:.....	
12.	Providing labour for cleaning of site and collecting malwa.	02	Nos.	
13.	Cartage for disposal of malwa up to 10km away from site.	8.10	Cum.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer



(Dinesh Kumar Raj)
Superintending Engineer


T. Roy
J.E.

No. 2064/MNO / of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 27/02/24 To 29/02/2024
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


T. Roy
J.E.