



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

1790/M10

QUOTATION NOTICE

दिनांक:.....
20/12/2023

To,

M/s.....
.....
.....

The sealed quotations are invited for Repairing of old damaged interlockings tiles and sewer chambers including other misc. work backside of trauma center KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Registered contractors of kgmu may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 21/12/2023.

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of dismantled as directed by engineer incharge.	6.60	Sqm.	
2.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	19.80	Sqm.	
3.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	0.54	Sqm.	
4.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	6.60	Sqm.	
5.	Fabrication of M.S frame for chambers including labour material t&p complete.	148.42	Kg.	
6.	P/L RCC work in covers 1:1.5:3 cement, coarse sand and stone aggregate.	0.38	Cum.	
7.	Mild steel work for reinforcement in plain cement concrete including binding,bending and cutting complete.	51.93	Kg.	
8.	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	1.11	Cum.	
9.	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineerin-charge.	32.71	Sqm.	
10.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	2.56	Cum.	
11.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	19.80	Sqm.	
12.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	26.40	Sqm.	
13.	P/F PVC pipe 100mm dia. 6kg pressure make of approved quality complete.	4.50	Rmt.	
14.	Providing welder with welding machine for repairing and refixing.	04	Nos.	
15.	Providing labour for cleaning of site and collecting malwa.	10	Nos.	

Ray
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----


दिनांक:


16.	Cartage for disposal of malwa up to 10km away from site.	10.80	Cum.	
-----	--	-------	------	--

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer



JE

No...../ of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 26/12/2023 To 21/01/2024
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


JE