



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: 1634/M-10/2023

दिनांक: 28/11/23

QUOTATION NOTICE

To,

M/s.....
.....
.....

The sealed quotations are invited P/F wall tiles in depatt of emg. Medicine and other misc. work at Shatabdi hospital phase-2 kgmu. the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 04/12/2023

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	15.32	Sqm	
2.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	2.52	Sqm	
3.	P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete.	2.52	Sqm	
4.	P/L floor/wall tiles in size 600x600mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 including grouting of joints with white cement and matching pigment etc.	15.32	Sqm	
5.	S/f anodized aluminum grill all including stainless steel wire gauze for including all labour material t&p etc.up to proper complete of work	6.87	Sqm	
6.	Providing labour charge for repairing of old aluminum door.	10.87	Sqm	
7.	Repairing of old false ceiling all complete fittings. Repairing of old false ceiling all complete fittings.	26.28	Sqm	
8.	S/F door closer for appd quality godrej or equivalent.	02	Nos	
9.	P/F inter locking metal false ceiling grid of hot dipped galvanized steel section consisting of main tee runner with suitable spaced joint "T" gates required length and of size 24x38mm made from 0.30mmthick sheet, spaced and 1200mm center to center and cross tee of size 24x25mm made of 0.30mm thick sheet, 1200mm long spaced between main "T" at 600mm center to center from to grid.	5.76	Sqm	
10.	S/F ACP sheet in palce of plain glass.	0.90	Sqm	
11.	Providing & fixing 5mm thick glass panes with glazing doors, windows, ventilators, shutter and partition etc. with EPDM rubber/neopren gasket etc. complete as per direction in charge	5.89	Sqm	
12.	S/F PVC connection 600mm long Prayag make	02	Nos	
13.	P/F brass ball valve 25mm dia high and low pressure with floats complete.	02	Nos	
14.	P/F 8mm dia SS jet flexible tube up to 1meter long.	01	No.	
15.	White glazed earthen ware(European type) W.C pan 505mm dia with seat cover of jaguar ESSCO, cera hindware	01	No.	
16.	Providing Sweeper for cleaning of mainhole and sewer line by sweeper with tools including disposal of garbage as per direction of site incharge	04	Nos.	

IRay
JET



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक:


दिनांक:

17.	Providing labour for cleaning of site and collecting malwa	06	Nos.	
18.	Cartage for disposal of malwa up to 10km away from site.	1.98	Cum	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer

Ref No - 1634/M-10/2023

No...../ of DT. 28/11/2023

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. 28/11/2023 To 04/12/2023.
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer


JE