



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

1992/ML-10

QUOTATION NOTICE

दिनांक:

18/01/2024

To,

M/s.....

.....

The sealed quotations are invited for Repairing of old damaged interlocking tile and other misc. work near entrance gate of resident hostel KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 24/01/2024

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	1.13	Cum.	
2.	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	14.40	Sqm.	
3.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	69.65	Sqm.	
4.	M-150 Class brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc.for proper completion of the work.	1.74	Cum.	
5.	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	2.33	Cum.	
6.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	0.49	Cum.	
7.	P/L 12mm cement plaster in 1:3 (1 Cement :3Coarse sand) finished with a floating coat of neat cement.	8.96	Sqm.	
8.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	9.33	Sqm.	
9.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	9.33	Sqm.	
10.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	69.65	Sqm.	
11.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	87.65	Sqm.	
12.	P/L of appd. Quality 60mm thick unipaver rubber molding interlocking tiles notless than 30MPa including leveling and dressing of surface to required level and slope, filling joints local sand and also including the cost of all material, labour T&p complete.	22.50	Sqm.	
13.	Providing labour for cleaning of site and collecting malwa.	06	Nos.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----


दिनांक:


14.	Cartage for disposal of malwa up to 10km away from site.	5.40	Cum.	
-----	--	------	------	--

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer



P. Roy
JE

No. 1992/MM10 / of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 18.01/2024 To 24.01/2024
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


P. Roy
JE