



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 Email : eng.civil@kgmcindia.edu

पत्रांक: -----

1949/MS/40

दिनांक:.....

12/6/224

QUOTATION NOTICE

To, M/s.....
.....
.....

The sealed quotations are invited for providing and fixing CPVC pipe for water cooler at transit hostel, khadra from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated

18/6/224

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, 20mm dia having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work	18.30	Rmt.	
2	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, 40mm dia having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work	79.30	Rmt.	
3	Making connection of G.I. distribution branch with G.I. main of size 25 to 40mm nominal bore by providing and fixing tee, including cutting and threading the pipe etc. complete.	01	No.	
4	Cutting hole up to 30x30 cm in walls including making good the same.	07	Nos.	
5	S/F PVC angle valve 15mm dia prayag make or equivalent.	02	Nos.	
6	P/F CPVC ball valve 40mm dia of prayag make.	01	No.	
7.	P/F PVC Tee 75mm dia.	05	Nos.	
8.	P/F PVC socket 75mm dia.	03	Nos.	
9.	P/F PVC elbow 75mm dia.	03	Nos.	
10.	P/F PVC pipe 75mm dia 6kg pressure.	36.59	Rmt.	
11.	P/F M.S clamp 75mm dia.	10	Nos.	
12.	Painting runway/taxi/ track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, including cleaning the surface of ail dirt, scales, oil, grease and other foreign material etc. and lining out complete. new work.	24.00	Sqm.	
13.	Providing plumber with helper for repairing of old fitting.	03	Nos.	
14.	Providing labour for cleaning of site and collecting malwa.	05	Nos.	

J.E



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 Email : eng.civil@kgmcindia.edu


पत्रांक: -----

दिनांक:.....

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer



(Dinesh Kumar Raj)
Superintending Engineer




No. 1949/MC of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 18/1/2024 To 18/1/2024
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Abhishek Sharma, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

