



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 1435/M-10

दिनांक: 16/10/2023

QUOTATION NOTICE

To,
M/s.....
.....
.....

The sealed quotations are invited for Repairing of floor tiles & Aluminum door and miscellaneous work at CCU 2, Anesthesia department, KGMU. The details of quotation notice can be seen at website www.kgmcindia.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 25/10/2023

Details of work as given below:-

S.NO	Particulars	Quantity	Unit	Rate
1	Dismantling stone flagged or tile floor, including stacking of dismantling material as per direction by the E/I.	25.92	Sqm	
2	Dismantling existing plaster including disposal of refuse as directed by the engineer- in- charge with in a distance of 60mtr (200 ft).	9.12	Sqm	
3	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	28.57	Sqm	
4	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand)	9.12	sqm	
5	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	9.12	Sqm	
6	Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete.	9.12	Sqm	
7	Providing and applying white cement based putty of average thickness 0.60mm of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete.	28.57	Sqm	
8	Oil bound distemper in Two coat	57.14	Sqm	
9	P/L ceramic floor tiles in size 600x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	25.92	Sqm	
10	Aluminium door repairing including cost of labour, T&P complete in all respect.	19.47	Sqm	
11	P/F 4mm thick ACP sheet in aluminum work for doors , windows, ventilators shutter and partitions etc with EPDM rubber neoprene gasket etc complete as per the architectural drawing and the direction of engineer-in-charge	0.46	Sqm	
12	P/F 5mm thick Glass panes in aluminum work for doors , windows, ventilators shutter and partitions etc with EPDM rubber neoprene gasket etc complete as per the architectural drawing and the direction of engineer-in-charge.	0.71	Sqm	
13	False ceiling Repair labour material complete etc.	10.24	Sqm	
14	Providing and fixing CP brass bib cock of approved quality and colour. 15mm nominal bore,	2	Nos	
15	P/f of steel sink (Eagle make) without Drainage board	1	Nos	

[Signature]



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

दिनांक:

1040x510x200mm complete.				
16	P/F Aluminium Sliding door bolt with 16mm dia and 250mm long.	4	Nos	
17	P/F American aluminium handle with screw 150mm long.	2	Nos	
18	P/F of S.S hinges 100mm long with stainless steel screw etc complete	12	Nos	
19	P/F of aluminum tower bolt 150mm long.	2	Nos	
20	PVC internal fitting of low level cistern ISI marked.	3	Nos	
21	P/F of door closer for appd. Quality godrej or equivalent.	14	Nos	
22	P/F Aluminium door stoppers	12	Nos	
23	Providing carpenter with helper for repairing of old door/window	2	Nos	
24	Providing plumber with helper repairing for sanitation work	2	Nos	
25	Sweeper per pair with tools	2	Nos	

Terms & Conditions

- 1.G.S.T and labour cess shall be paid or deducted as per rules applicable.
- 2.The work will be completed within given time.
- 3.Quantity can be increase or decrease as per requirements.
- 4.Conditional quotations are liable to be rejected.
- 5.The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)
Superintending Engineer

[Signature]

No. 1435 M-10 of DT. 16/10/2023

Copy for information and necessary action to:-

- 1.Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 16/10/2023 To 25/10/2023.
3. Sri Shailendra Singh, Executive Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Anjani kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
6. Notice Board.

(Dinesh Kumar Raj)
Superintending Engineer

[Signature]