



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: 1656/10

दिनांक: 30/11/2023

QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for p/f m.s stair in archival room and aluminum window in office including other misc. work at pathology department the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 01/12/2023.....

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling of old door / windows chaukhats with hold fast & including stacking of dismantled material directed by the engineer incharge.	01	No.	
2.	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	4.48	Sqm	
3.	Mild steel work for reinforcement in plain cement concrete including binding, bending and cutting complete.	4.63	Kg	
4.	P/L RCC work in lintel in 1:1.5:3 cement, coarse sand and stone aggregate.	0.02	Cum.	
5.	P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete.	0.85	Sqm	
6.	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete.	1.77	Rmt	
7.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	10.32	Sqm	
8.	Applying one coat white cement on new surface.	10.32	Sqm	
9.	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	10.32	Sqm	
10.	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	12.41	Sqm	
11.	P/F anodised aluminum work for doors, window, ventilators and partitions with extruded built up standerd tubular section Z section and other section of approved make conforming to IS: 733 and is: 1285 fixing with dash fasteners of required dia size including necessary fittings up the gaps at junctions I.E at top, bottom, and sides with required EPDM rubber/ neoprene gasket etc. complete.	15.44	Sqm	
12.	Providing & fixing 5mm thick glass panes with glazing doors, windows, ventilators, shutter and partition etc. with EPDM rubber/ neopren gasket etc. complete as per direction in charge	0.59	Sqm	
13.	Supply and fixing anodised aluminum butt hinges 125x75x4mm.	04	Nos.	
14.	P/F of aluminum tower bolt 150mm long	04	Nos	
15.	P/F aluminum handles with screw 125mm long.	02	Nos	
16.	S/f anodized aluminum grill all including stainless steel wire gauze for including all labour material t&p etc.up to proper complete of work	1.09	Sqm	
17.	Fabrication of M.S frame structure with hollow pipe, angle, flat including labour material T&p complete.	254.33	Kg	
18.	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	8.25	Sqm	

J Roy
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----


दिनांक:.....

19.	P/F carbon steel galvanized dash fashner of 10mm dia 80mm long including drilling of hole in frame concrete etc.	04	Nos	
20.	P/F G.I elbow 50mm dia	08	Nos	
21.	P/F G.I Union 50mm dia	02	Nos	
22.	P/F brass ball valve 25mm dia high and low pressure with floats complete.	02	Nos	
23.	S/F of C.I pipe 100mm dia HEPCO make.	4.30	Rmt	
24.	S/F C.I Plain bend 100mm dia HEPCO make	01	No.	
25.	S/F of C.I coller 100m dia. HEPCO make	01	No.	
26.	Providing Plumber with helper for repairing of old fitting and making water connections	02	Nos	
27.	Cartage for disposal of malwa up to 10km away from site.	2.17	Cum	
28.	Providing labour for cleaning of site and collecting malwa	02	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


Yours faithfully


(Suresh Kumar) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer

No. 1650/MC of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administratiion Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 30/11/2023 To 04/12/2023
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer


JE