



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: 2043/M/10

दिनांक: 31/01/2024

QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for providing and fixing Flush door, painting and other misc. work at Eye opd kgmu the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 07.02/2024.... Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling of old door / windows chaukhats with hold fast & including stacking of dismantled material directed by the engineer incharge.	01	No.	
2.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.02	Cum	
3	P/L 12mm thick cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&P etc. for proper completion of work.	4.11	Sqm	
4.	Fabrication of M.S structure with M.S window with welding complete.	19.22	Kg	
5	P/F 30mm flush door shutters ISI marked stainless steel butt hinges with necessary non decorative with frame of 1st class hard wood and well matched commercial 3ply veneering with vertical grains or croos bands and face veneers on both faces of shutters	2.21	Sqm	
6	P/F stainless steel door handle with Screw 150mm long.	02	Nos	
7	P/F Stainless steel tower bolts with 10mm dia rod & Screw 150 mm long.	01	No.	
8	P/F Stainless steel sliding bolts with 16mm dia nuts& bolts 250mm long.	01	No.	
9	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	261.80	Sqm	
10	P/L cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	261.80	Sqm	
11	Distempering with oil bound distemper two coat of approved brand on old Surface togive an even shade including all material, labour T&P etc. complete.	462.69	Sqm	
12	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	74.97	Sqm	
13	Providing carpanter with helper for Repair of old doors and windows.	01	Nos	
14	Cartage for disposal of malwa up to 10km away from site.	2.72	Sqm	
15	Providing labour for cleaning of site and collecting malwa	02	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

दिनांक:.....

5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

AM

DKR

(Anupam mishra) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer

No. 2043/M/10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 31/01/2024 To 27/02/2024
3. Sri Yashwant singh, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Sumit kanaujia, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

AM

DKR

(Anupam mishra) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer