



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003



कार्यालय अधीक्षण अभियन्ता(सिविल), निर्माणविभाग  
फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक: 1958 / एम-10 / 2023

दिनांक: 12/01/2024

## QUOTATION NOTICE

To,

M/s.....  
.....  
.....

The sealed quotations are invited for P/L floor tiles in corridor. repairing & painting work (dean room), ground floor of Dean Dental at KGMU at kgmu from the registered contractor of KGMU. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned, by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated. 19/01/2024

Details of the work as given below-

S.No	Particular	Qty	Unit	Rates
1.	Dismantling tiled floor, including base concrete and including stacking of dismantled materials as directed by the Engineer-in-charge within a distance of 50 metres (200ft).	33.60	Sqm	
2.	P/L vitrified floor tiles in size 600x600mm with water absorption less than 0.08% and confirming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	36.00	Sqm	
3.	Scrapping old white or coloured wash etc including disposal of refuse material as directed by Engineer in charge	80.00	Sqm	
4.	P/L of Birla white putty for making good smooth surface.	80.00	Sqm	
5.	Distemping with oil bound distemper two coat of approved brand on old surface to give and even shade including all material, labour T&P etc. complete.	202.45	Sqm	
6.	Enamel painting in two coat	2.95	Sqm	
7.	Polishing in high gloss/matt finish melamine clear polish on wood work in required color/wooden shade texture with 1 <sup>st</sup> coat of melamine polish is applied with spray gun using melamine clear polish and melamine thinner in required proportion. This 1 <sup>st</sup> coat is allowed to dry for 24 hrs then this dry surface is again fine wet rubbed smooth, which is further allowed to dry for 12 hrs. The final melamine polish is applied with compressor pressure spray gun using melamine clear polish and melamine thinner mixed in required proportion complete as per direction of Engineer-in-charge. (Final coat to be done in 1 or 2 layers without gap of time).	6.72	Sqm	
8.	Cartage for disposal of malwa upto 10 km away from the site.	3.15	Cum	
9.	Providing labour for cleansing of site and collecting malwa.	4.00	Nos.	

### Terms & Conditions

1. G.S.T and labourcess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

(Anupam Mishra)  
Executive Engineer

Yours Faithfully

(Dinesh Kumar Raj)  
Superintending Engineer

No...../

Date.....

Copy for Information and necessary action to:



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003



कार्यालय अधीक्षण अभियन्ता(सिविल), निर्माणविभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक:.....1958/एम-10/2023

दिनांक:.....

1. Registrar, K.G.M.U, U.P. Lucknow
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. 12/01/2024 To 19/01/2024
3. Sri Anupam Mishra, Executive Engineer, Works deptt. K.G.M.U, U.P. Lucknow
4. Sri Yashvant Singh, Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
5. Sri Kartikey Upadhyay, Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Notice Board.

(AnupamMishra)  
Executive Engineer

(Dinesh Kumar Raj)  
Superintending Engineer