



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ-226003
कार्यालय अधिशासी अभियंता (विद्युत/यंत्रिक)

पत्रांक... 160/EE (EM)

दिनांक 25/10/2023

Urgent Quotation Notice

Sub: - To Jointing of faulty cable of CV Hall near Hostel & New Mortuary substation between Cobalt substation, KGMU, Lucknow.

Kindly submit your Quotation/Estimate for providing the following work in sealed envelope to the undersigned in the interest of patient care/institution within 3 days from the date of dispatch.

S.No.	Particulars	Qty.	Rate in each	Amount in Rs.
1	To locating the fault with help of 11KV H.T. fault locating machine.	01 Job		
2	To cable jointing & 240sq.mm. X 3.5 core straight through jointing kit.	04 Nos.		
3	Digging of flooring for taking out the faulty cable of C.V. hall.	01 Job.		
4	To trace the main cable of 240sq.mm. For CV hall from mortuary substation via new substation after digging the cable after removing the 10 nos main cables of 240 & 300sq.mm.	1 Job.		
5	Testing, Meggering, & commissioning the cable 240sq.mm. of CV hall after jointing 4 nos of cable with dressing & underground cable.	1 Job		
Total				

Terms & Conditions:-

1. G.S.T. : As Applicable.
2. All the works shall be completed within the given time period as per work order.
3. Quantity can be increase or decrease as per requirements.
4. All the works shall be carried out as per PWD specifications.
5. Contractor having experience of similar nature and style electrical work in 300 bedded Govt./semi Govt. Hospital

Your Faithfully

Executive Engineer (Electrical)
K.G.M.U.U.P., LUCKNOW

No.....of DT.....

Copy for information and necessary action to:-

1. Dr. Richa Khanna, Faculty In charge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from:.....
2. Notice board.

Executive Engineer (Electrical)
K.G.M.U.U.P., LUCKNOW