



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक: 2241 / एम-10 / 2024

दिनांक: 11/03/2024

## QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotations are invited for P/F of new stainless steel sink including platform and other misc. work at 3<sup>rd</sup> floor Paraplegia ward RALC at KGMU at kgmu from the registered contractor of KGMU. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated. 18/03/2024

Details of the work as given below-

S.No	Particular	Qty	Unit	Rates
1.	12mm thick plaster 1:6 cement C-Sand on wall with cement and coarse sand including supply of all material labor and T&P etc. for proper completion of the work.	3.62	Sqm	
2.	R.C.C. Slab in 1:1½:3 cement C-Sand stone aggregate.	0.07	Cum	
3.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	1.23	Sqm	
4.	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. 11.56.1 Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	0.93	Sqm	
5.	P/F double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia. M.S Tube placed 1.5 metre center to center, horizontal and vertical tubes joint with cup and lock system with M.S Tubes, M.S Tubes chalis, M.S clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/or pointing and/or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge.	18.00	Sqm	
6.	Mild Steel work 10/12mm dia as for reinforcement.	4.34	Kg.	
7.	Repairing of old Aluminum Door and window	3.15	Sqm	
8.	Making the opening in brick masonry for door, windows including dismantling in floors or walls by cutting masonry and making goods to the damages to the wall, flooring and jams complete, to match existing surface including disposal of mulba/rubbish to the nearest municipal dumping ground under the direction of Engineer in charge.	1.32	Sqm.	
9.	P/F CPVC 20 mm nominal outer dia. having thermal stability for hot&cold water supply including CPVC plain & brass threaded fittings with one step CPVC solvent cement, trenching, refilling and testing of joints complete as per direction of Engineer in Charge.	14.75	Rmt	
10.	Applying one coat of water thinnable cement prima of approved brand on new wall surface.	3.62	Sqm	
11.	P/L white cement based putty of avg. thickness 1mm of approved brand on new surface.	3.62	Sqm	
12.	Distemping with oil bound distemper two coat of approved brand on old surface togive and even shade including all material, labour T&P etc. complete.	3.62	Sqm	





# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक:...../एम-10/2024

दिनांक:.....

	board as per IS 13983 with C.I. brackets stainless steel plug 40mm, including painting of fittings and brackets, cutting an making good the walls wherever required.		
14.	P/F pvc pipe 50mm dia.	14.75	Rmt
15.	P/F swiss welded mesh 1'' x1'' 10 gauze with 20x5mm flat iron beading including all material labour T&P complete.	3.15	Sqm
16.	Fabrication of M.S. frame with M.S. angles.	27.06	Kg
17.	Water Proofing treatment for joints of C.I/PVC pipe with resin based water proofing chemical including fiber glass matt and fine powder width of chemical coating on joint not less than 250mm on any dia. of pipe. Applying chemical coating on joint in three layers up to 3 to 4mm and also including filling of gap between collar and pipe with resin based putty including fiber glass matt.	10.00	Nos.
18.	P/F PVC Elbow 50mm dia	3	Nos.
19.	P/F pvc bib cock 15mm dia.	1	Nos.
20.	P/F PVC pipe 100mm dia 6kg pressure ISI make	1.00	Rmt.
21.	P/F of G.I. pipe 15mm dia. complete with fittings 'B' class.	4.50	Rmt
22.	S/F PVC Nahani Trap 100mm dia.	1	No
23.	S/F PVC Socket 100mm dia.	1	No
24.	P/F of G.I. Long screw 15mm dia.	1	No.
25.	P/F of G.I. Tee 15mm dia.	2	No.
26.	P/F of Iron hinges 125mm long ISI make.	4	Nos.
27.	P/F of G.I. Socket 15mm dia.	2	No.
28.	Providing and fixing of P.V.C. waste pipe 32mm dia. 600mm long.	1	Nos.
29.	Providing and fixing P.V.C. Connection 600mm long.	1	Nos.
30.	Providing labour for miscellaneous work.	4	Nos.
31.	Providing plumber with helper for sanitary fitting	2	Nos.
32.	Cartage for disposal of malwa upto 10 km away from the site.	3.15	Cum

## Terms & Conditions

1. G.S.T and labourcess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

*(Signature)*

(Anupam Mishra)  
Executive Engineer

Yours Faithfully

*(Signature)*  
(Dinesh Kumar Raj)  
Superintending Engineer

No. 2241 / .....

*(Signature)*  
JE

Date 11/03/2024

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 11/03/24 To 18/03/2024
3. Sri Yashvant Singh, Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
4. Sri Kartikey Upadhyay, Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
5. Notice Board

*(Signature)*

(Anupam Mishra)  
Executive Engineer

*(Signature)*

(Dinesh Kumar Raj)  
Superintending Engineer