



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक: 1990 / एम-10 / 2024

दिनांक: 18/11/2024

## QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotations are invited for Providing new flush doors,pvc pipe,G.I pipe.and other misc. work at RALC and Rheumatology at KGMU at kgmu from the registered contractor of KGMU. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 24/11/2024

Details of the work as given below-

S.No	Particular	Qty	Unit	Rates
1.	Grouting the joints of flooring tiles having joints of 3mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shape (0.10 kg of hardener and 0.20kg of resin per kg) , including filling/grouting and finishing comp:ete as per direction of Engineer-in-charge.	24.66	Sqm	
2.	P/F CPVC 20 mm nominal outer dia. having thermal stability for hot&cold water supply including CPVC plain & brass threaded fittings with one step CPVC solvent cement, trenching, refilling and testing of joints complete as per direction of Engineer in Charge.	6.05	Rmt	
3.	P/F of Flush door decorative type, core of blackboard construction with frame of 1 <sup>st</sup> class hardwood and well matched teak 3ply. 32mm. thickness water proof complete etc.	4.18	Sqm	
4.	Removing of aluminium partition from one place to another.	12.60	Sqm	
5.	Enamel painting in two coat	15.09	Sqm	
6.	P/F PVC pipe 100mm dia 6kg pressure ISI make	3.00	Rmt.	
7.	P/F PVC Elbow 100mm dia	2	Nos.	
8.	P/F of G.I. pipe 25mm dia. complete with fittings 'B' class.	12.00	Rmt	
9.	Providing and fixing G.I. Socket 25mm dia.	3.00	No.	
10.	P/F of G.I. Elbow 25mm dia.	3	Nos.	
11.	P/F of G.I. Long screw 25mm dia.	1	No.	
12.	Providing and fixing of P.V.C. waste pipe 32mm dia. 600mm long.	4	Nos.	
13.	Providing and fixing C.P. Brass spandle for basin mixer/wall mixer.	4	Nos.	
14.	Providing and fixing C.P. Floor Jali 100mm dia.	6	Nos.	
15.	P/F waste jail 100mm dia.	3	Nos.	
16.	P/F sink jail 100mm dia.	5	Nos.	
17.	P/F double scaffolding system (cup lock type) on the exterior side of building/structure,upto 25 metre height,above ground level,including additional rows of scaffolding in stepped manner as per requirement of site,made with 40mm dia. M.S Tube placed 1.5 metre center to center,horizontal and vertical tubes joint with cup and lock system with M.S Tubes,M.S Tubes challis,M.S clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable conditionfor execution of work of cleaning and/or pointing and/or applying chemical and removing it thereafter.The scaffolding system shall be stiffened with bracings,runners.connecting with the building etc,wherever required,if feasible	51.15	Sqm	



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक:..... / एम-10 / 2024


दिनांक:.....


18.	Providing carpenter with helper for repairing of old door/window and making wooden wardrobe.	2	Nos.	
19.	Providing labour for miscellaneous work.	20	Nos.	
20.	Providing of chemical for removal of plant.	10	Ltr	
21.	Providing plumber with helper for sanitary fitting	2	Nos.	
22.	Providing Sweeper for cleaning of N trap and P trap & for cleaning of old seewage.	4	Per day	
23.	Cartage for disposal of malwa upto 10 km away from the site.	9.45	Cum	

### Terms & Conditions

1. G.S.T and labourcess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours Faithfully

  
(Anupam Mishra)  
Executive Engineer


  
(Dinesh Kumar Raj)  
Superintending Engineer

No..... 1990/M<sup>10</sup>

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 18/1/24 To 21/1/2024
3. Sri Anupam Mishra, Executive Engineer, Works deptt. K.G.M.U, U.P. Lucknow
4. Sri Yashvant Singh, Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
5. Sri Kartikey Upadhyay, Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Notice Board.

  
(Anupam Mishra)  
Executive Engineer

  
(Dinesh Kumar Raj)  
Superintending Engineer